QUOTATION

Item #L-42

A.R. McDiarmid Civic Complex Fibre Relocation & Foundation Waterproofing

A Site Visit will be held on Tuesday, October 20, 2026 . Refer to Instructions to Bidders #3 – Site Visit for further details.

A.R. McDiarmid Civic Complex Fibre Relocation & Foundation Waterproofing

TABLE OF CONTENTS

1. DEFINITIONS 1
2. ENQUIRIES 1
3. SITE VISIT 1
4. PRICING 1
5. RECEIPT OF QUOTATIONS 1
6. SUBMISSION OF QUOTATIONS 1
7. ADDENDA 2
8. ALTERNATE BIDS 3
9. WITHDRAWAL OF QUOTATIONS 3
10. REJECTION OF QUOTATIONS 3
11. AWARD AND EXECUTION OF QUOTATIONS 3

PART B. – SUPPLEMENTAL CONDITIONS 4

A) Application 4
B) Local License Requirements 4
C) Schedule 4
D) Selection Process/Criteria 4
E) Submittal Requirements 5
F) Cost Adjustment 5
G) Insurance and Indemnification Requirements 5
H) Warranty 6
I) Contractor's Declaration 6
J) Public Health Act – Section 67 Requirements 6

Appendix 1 – Specifications

Bid Form

The following information is available for download on the City of Brandon website https://purchasing.brandon.ca:

1. A.R. McDiarmid Fibre Relocation & Foundation Waterproofing
2. Section 09-010 Fibre Optics

PART A. - INSTRUCTIONS TO BIDDERS

1. DEFINITIONS

Where in the Quotation Documents where the singular or masculine are used, the same shall be construed as meaning the plural or the feminine or the neuter as the context may reasonably require, and where the following terms are used, the intent and meaning shall be, unless the context otherwise requires, as follows:

"Bidder" means any person submitting a Bid Submission for work, which includes but is not limited to vendor, supplier, firm, contractor, architect, consultant, proponent, or tenderer.

"Bid Submission" means an offer from a Bidder in response to a Bid Solicitation.

"City" means the Municipal Corporation of the City of Brandon.

"Contractor" means supplier, vendor, consultant or service provider who provides goods, services or construction to the City of Brandon.

"Contractor Personnel" means all individuals provided by the Contractor to perform services under the contract including employees, representatives, and consultants of the Contractor or subcontractor and any other individual for whom the Contractor is responsible for by law.

"Quotation Documents" means the Invitation to Bid, these Instructions to Bidders, Supplemental Conditions, the Bid Form, Specifications, and all Addenda.

2. ENQUIRIES

Administrative inquiries and requests for clarification of the Bid process shall be made to the Procurement Specialist in writing at **purchasing@brandon.ca** and must be received not less than five (5) calendar days prior to the date for closing of Bids.

3. SITE VISIT

A site visit will be held on **Tuesday, October 20, 2026** at 2:00 p.m. at the at the A.R. McDiarmid building located at 638 Princess Avenue. Please use the west entrance off of 7th Street. Sign-in will commence at 1:45 p.m. Attendance at the site visit is not mandatory; however, all interested parties are encouraged to attend as this will be the only opportunity to view the sites.

4. PRICING

Prices shall be in Canadian Funds and shall be the total cost to the City of Brandon, including all applicable Federal and Provincial Taxes, duties, license costs, fees, insurance, workers compensation, vacation pay and all other charges, costs and assessments with all items being F.O.B., A.R. McDiarmid Civic Complex, 638 Princess Avenue, Brandon, Manitoba. It is the Bidder's sole responsibility to determine whether or not taxes are applicable.

5. RECEIPT OF QUOTATIONS

The Quotation must be received by the method indicated below before 5:00:00 p.m. local Brandon time, **Thursday, October 29, 2026** to be accepted as a bona fide Bid Submission.

Bid Submissions must be received by the City before the stipulated closing time. Late Bid Submissions will not be accepted.

6. SUBMISSION OF QUOTATIONS

The Bidder shall submit their Quotation on original or unaltered copies of the Bid Form provided herein. Any information provided by the City on any form must not be altered by the Bidder unless instructed to do so by written Addenda. The Bidder shall initial and date each correction, change, and/or erasure on the Bid Form. The Bid Form shall be clearly signed by the Bidder and shall clearly indicate the address of the Bidder, the Bidder's telephone number, and the date on which the Bid Form was signed by the Bidder.

Bids submitted by a partnership shall be signed and sealed in the name of the partnership by the authorized signing and sealing officers of the company. The name of the company and the names of the company along with titles of the signing officers shall be clearly printed in the spaces provided on the Bid Form.

The Bid Submission shall be submitted to the City by the following method:

Via Online Bidding Platform (E-submission)
One (1) copy of an electronic Bid Submission in .PDF format shall be submitted via the "Submit Online Bid" link for the associated Bid Opportunity on the City of Brandon Purchasing & Tenders website: https://purchasing.brandon.ca.

The City utilizes an online bidding platform where electronic Bid Submissions may be submitted until the closing time indicated herein for receipt of Quotations.

The procedure for submitting electronic Bid Submissions can be viewed on the City's Purchasing & Tenders website or by clicking here. Failure to follow the procedure as indicated may result in a Bid Submission not being received. Any failure or delay in the transmission or storage of an electronic Bid Submission is the sole responsibility of the Bidder and not of the City.

The City will ONLY accept electronic Bid Submissions uploaded to the City's online bidding platform. Electronic Bid Submissions sent via e-mail will **not** be accepted. If a Bidder encounters issues uploading an electronic Bid Submission, contact the City's Procurement Services Department at 204-729-2251.

A Bid Submission will only be considered to have been submitted once it has been received by the City in the online bidding platform. The time the Bid Submission is received shall be determined by the City's server time, which is linked to National Institute of Standards & Technology time. Bidders are advised the time the electronic Bid Submission is received is based on when the Bid Submission is received by the City's server.

A confirmation webpage will display advising the Bid Submission was submitted successfully and a confirmation email will be sent. Bidders should not consider their Bid Submission to have been submitted if the confirmation webpage does not display and a confirmation email is not received.

Bid Submissions received via the online bidding platform are held securely and are inaccessible by Procurement Services staff until after the stipulated closing date and time.

Mail, Courier, Hand Delivered, Facsimile or E-mail Submissions Are Not Accepted.

7. **ADDENDA**
The City shall have the right to amend the Quotation Documents prior to the date set for receipt of Bids. Revisions or clarifications will be issued in the form of Addenda forwarded to all registered recipients of the Documents. Verbal and other interpretations or clarifications will be binding only when confirmed by written Addenda. Bidders shall acknowledge receipt of all Addenda to the Quotation Documents in the space provided on the Bid Form. Failure to acknowledge all Addenda may cause the Quotation to be rejected.

8. **ALTERNATE BIDS**
Alternate Bid Submissions are accepted. A separate Bid Form and Appendix 1 offering an alternate may be attached to the Bid Submission, but a Bid Submission in the proper form must be offered complete and in no way be made conditional upon the terms contained in the separate Bid Form and Appendix 1. A note "See Alternate Attached" may be added to the Bid Submission.

9. **WITHDRAWAL OF QUOTATIONS**
A Bidder shall be permitted to withdraw their Quotation, without penalty, if such request is received in writing by the Procurement Specialist, prior to the time specified herein for receipt of Bids:

The City of Brandon
410-9th Street
Brandon, MB R7A 6A2

Ph: 204-729-2251
FX: 204-726-8546
E: purchasing@brandon.ca

The City shall retain the Quotation until after the time specified herein for the receipt of Quotations. The submission will be opened to verify that the name and signature of the person requesting the Quotation be withdrawn is the same as the name and signature of the person who submitted the Quotation. If the information is the same, the Procurement Specialist will declare the bid withdrawn.

10. REJECTION OF QUOTATIONS
The City reserves the right to reject any or all Quotations, the City in its sole discretion may reject as non-compliant any Quotation which contains omissions, erasures; is ambiguous or unclear as to meaning or intent; is incomplete, illegible, conditional or contains a qualifier; contains any non-requested alterations or additions to the information provided by the City; is obviously unbalanced; or fails to comply sufficiently with the Instructions to Bidders. The City may, in its sole discretion, waive any and all defects, informalities, and accept any Quotation, as compliant, which it considers is in the best interest of the City of Brandon.

11. **AWARD AND EXECUTION OF QUOTATIONS**
The City reserves the right to cancel this Quotation at any time. The Award of the Quotation, if it is to be awarded, shall be made within sixty (60) calendar days of the date on which the Quotations were opened, unless an extension of the said sixty (60) days is mutually agreed upon in writing between one or more Bidders and the City. Should no award be made within the said sixty (60) days or within any mutually agreeable extension thereof, then all Bidders shall be relieved of any obligation to enter into a Contract.

The award of the Quotation will not be binding until the successful Bidder has received written notification of the award of the Quotation from the Procurement Specialist of the City of Brandon. No other act of the City shall constitute an award of the Quotation. The award of the Quotation shall fall under the governing laws of the Province of Manitoba.

The lowest or any Bid will not necessarily be accepted.

PART B. – SUPPLEMENTAL CONDITIONS

The City of Brandon
For
A.R. McDiarmid Civic Complex Fibre Relocation & Foundation Waterproofing

A) Application

A.1 The City requires pricing for fibre relocation, foundation waterproofing and optional excavation and sidewalk repair at the AR McDiarmid Building located at 638 Princess Avenue, Brandon, MB.

A.2 The Contractor shall provide all the necessary material, equipment and labour to perform the Work.

A.3 It is the responsibility of the Contractor to abide by the construction requirements as stated in the City of Brandon Engineering Department Standard Construction Specification Book and General Conditions of the Contract. Documents are available in electronic form on the City of Brandon website https://purchasing.brandon.ca.

A.4 It is the responsibility of the Contractor to abide by all City of Brandon Planning, Property & Buildings Department requirements, by-laws and codes. All required permitting and associated costs related to meeting City of Brandon Planning, Property & Buildings Department's requirements are the responsibility of the Contractor. The Contractor shall not commence Work until all required permits have been applied for and approved.

A.5 The Contractor must comply with all Canadian Federal, Provincial, Municipal Safety Regulations and Standards.

A.6 Appendix 1 indicates the minimum specifications.

B) Local License Requirements

Any persons conducting business within the City of Brandon from a Brandon residential address must have a valid Business License. This includes agents from companies that are not based in Brandon but where the agent is conducting their business from a Brandon address. Non-compliance will result in rejection of a Bid.

All successful Bidders of construction or service work for the City of Brandon, whether Brandon-based or otherwise, must obtain a City of Brandon License. This is not applicable to suppliers from outside of the City who supply the City of Brandon with goods for the sole use of the City.

Any inquiries on the above should be directed to Municipal Licensing at 204-729-2230.

C) Schedule

The City of Brandon intends to evaluate the Quotations and provide recommendations to Procurement Services within four (4) weeks of Quotations closing.

D) Selection Process/Criteria

a) Cost; and
b) Completion date.

Award of this Quotation is subject to City Council approval.

The City reserves the right to contact or interview any or all Bidders to clarify their Bid Submission.

The City will normally award contracts to the lowest competent Bidder meeting the required specifications. However, the City retains the right to reject any or all Bids and take into consideration past performance of bidders on similar contracts, both in and out of the City and such other factors the City considers relevant including the timing of services to be provided.

E) Submittal Requirements
Limit the submittal to 8½"x11" pages. Failure to include the following information will render the Bid Submission non-compliant.

Please include the following:
1) Bid Form.

F) Cost Adjustment
1) The Contract Price shall be adjusted (increase or decrease) for any change in law or tax imposed under:
    a. the Excise Act
    b. the Excise Tax Act
    c. the Customs Act
    d. the Customs Tariff Act
    e. the Retail Sales Tax Act

    that occurs **after** the Closing Date that directly affects the goods supplied or the cost of the goods to the Successful Bidder.
2) The Successful Bidder shall substantiate the value by providing the Contract Administrator relevant records to verify the change in price.
3) The Successful Bidder will be required to provide satisfactory proof that alternative options were investigated in order to reduce or eliminate price changes for tariffs.

G) Insurance and Indemnification Requirements
Workers Compensation Number must be current and in good standing.

The Contractor shall be deemed the prime contractor for the project and is solely responsible for construction and public safety at the site and for securing the site at all times to prevent public access. The Contractor shall carry out the work in accordance with the construction safety code in force at the place of work and in accordance with the applicable Workplace Safety and Health Act Regulation for Manitoba. The Contractor shall insure that when work is stopped, the Contractor leaves the Site in a safe and secure manner. At the discretion of the Building Maintenance Chargehand or their designate, may require additional safety precautions over and above the codes during the construction.

The Contractor shall at their own expense obtain Comprehensive General Liability (Occurrence form) policy written in the Contractor's name and including the City of Brandon as an additional insured in the amount of not less than five million dollars ($5,000,000) inclusive for bodily injury and/or property damage for any one occurrence or series of occurrences arising out of one cause. Legal or defence costs incurred in respect of a claim or claims shall not operate to decrease the limit of liability. A Certificate of Insurance shall be provided prior to commencing work.

Automobile Liability Insurance in respect of vehicles that are required by law to be insured under a contract by a Motor Vehicle Liability Policy, shall have limits of not less than two million dollars ($2,000,000) inclusive per occurrence for bodily injury, death, and damage to property, covering all vehicles owned or leased by the Contractor, in the following forms:

1. Standard Non-Owned Automobile Policy including Standard Contractual Liability Endorsement. This may be attached to the General Liability Insurance policy.
2. Standard Owner's Form Automobile Policy providing Third Party Liability and Accident Benefits Insurance and covering licensed vehicles owned or leased by the Contractor.

The Automobile Liability Insurance shall be maintained continuously from commencement of the Work until the date of the expiry of the Warranty Period.

H) Warranty

The Contractor shall unless specifically stated otherwise in the contract documents at their sole cost and expense maintain the Work against any and all defects and deficiencies that may arise for a period of twelve (12) months from date of certificate of final completion of work.

Upon notification by the City or their designate the Contractor shall at their sole cost and expense remedy any defects or deficiencies identified by the City or their designate during the warranty period and any damage that may arise or result from defect or deficiencies or as a result of the correction of same.

The Contractor shall provide manufacturers warranty information for all products upon completion of the Work.

I) Contractor's Declaration

The Contractor declares that in bidding for the Work and in entering into a Contract with the City, they are aware of any Orders issued under section 67 of the Public Health Act and has taken all necessary steps to ensure compliance with said Orders. The Contractor shall adhere to any procedure and/or protocols by the City that may exceed the requirements set forth in the aforementioned Orders while on City property. The Contractor shall regularly check the Province of Manitoba Public Health Act webpage for updates to section 67 and ensure compliance with any future Orders.

The Contractor also declares that in bidding for the Work and entering into a Contract with the City, they shall adhere to any requirements set forth by the City that may exceed the requirements in the Orders issued under section 67 of the Public Health Act.

All public health orders related to section 67 procedures and/or protocols are the responsibility of the Prime Contractor. As the Prime Contractor, the Contractor shall ensure any Contractor's Personnel are also in compliance.

J) Public Health Act – Section 67 Requirements

The City reserves the right at any time to perform random audits to ensure the Contractor and the Contractor's Personnel are in compliance with the City's requirements.

Any and all costs associated with compliance to the City's requirements while performing the Work are to be borne by the Contractor.

Safety Measures

The Contractor and Contractor's personnel are required to reduce safety hazards associated with section 67 orders such as but not limited to providing personal protective equipment (PPE), physical distancing, and monitoring for symptoms.

APPENDIX 1

SPECIFICATIONS
ITEM #L-42

A.R. McDiarmid Civic Complex Fibre Relocation & Foundation Waterproofing

The following specifications are the minimum specifications acceptable by the City. Actual specifications may exceed these specifications. Should the quote have additional features that are not in the specifications, include them with the Bid Submission so the Quotation can be fairly evaluated.

SECTION 01002 SCOPE OF WORK

PART 1: GENERAL

1.1 OTHER CONTRACT DOCUMENTS

.1 The General Conditions of the Contract, the Supplemental Conditions, Specifications, and Drawings attached hereto shall apply to and be part of this Section. If there is any conflict between this Section and either of the above, this Section shall govern.

.2 Where the City of Brandon Standard Construction Specifications refer to the Supplemental Conditions or the Special Provisions, it shall now mean Section 01002, Scope of Work.

1.2 THE WORK

.1 The Work includes the removal of existing underground utilities servicing the AR McDiarmid Building, non structural repair of the foundation wall affected by the utility removals, and completion of all associated fibre optic relocation, installation, and restoration work.

1.3 SCHEDULE OF WORK

.1 The Work shall be scheduled at the discretion of the Contractor, subject to the provisions as specified herein.

.2 The Contractor shall advise the City a minimum of five (5) Working Days in advance of his intention to commence or terminate Work. Once the Work has begun, it shall be advanced diligently with a view of completing the Work or restoring the infrastructure to full use in the shortest possible time.

.3 Prior to commencement of each stage of construction on any project, the Contractor shall obtain clearance from the City that the previous stage is ready to receive new Work, and that there are no reasons of weather or other matters outside the City's control which would preclude commencement of the new Work.

1.4 OTHER UTILITIES

.1 The drawings are intended to show the existence and location of utilities in the right of ways at the date of drawing; however, not all utilities may be shown or additional utilities may have been added since the Drawings were made. The Contractor shall make all necessary enquiries and give all requisite notice to utilities prior to commencing the Work. Any Work or cost required to locate or expose a utility after the Contract has been awarded shall be borne entirely by the Contractor.

1.5 SITE CONDITIONS & COORDINATION

.1 Prior to commencing any Work, inspect field conditions, obtain and confirm actual Site dimensions and examine surface conditions which may be affected by the Work, whether buried or surface utilities, signs, structures or any other object which may be in conflict with the Work.

.2 Take extra precaution near any natural gas mains that are located within the limits of the Work. Limits of excavation around gas mains may differ on each Site and shall be as directed by Manitoba Hydro once construction begins on any one project.

.3 Take extra precaution near overhead wires that are located within the limits of the Work. Limits of excavation near overhead wires may differ on each Site and shall be as directed by Manitoba Hydro once construction begins on any one project.

.4 The limits of the Work will be established prior to the start of any excavation, and the Contractor shall be required to maintain the Site in a neat and tidy condition with cleanup completed each day.

.5 Coordinate activities of sub-trades and work by others as required to expedite the Work.

.6 Coordinate activities between Contractor and other Works and/or Contractors in adjacent areas. Contractor will not have exclusive rights to the general area.

.7 The City shall be given a minimum of 48 hour notice before the contractor wishes to disconnect or cut the fibre optics cable. The contractor shall complete the work in a manner that allows for an interruption to fibre optic services for no more than 72 hrs.

PART 2: PRODUCTS

2.1 CONDUIT

.1 Conduit shall be as specified in Section 09-010 Fibre Optics.

2.2 FIBRE OPTIC CABLE

.1 Fibre Optic Cable shall be as specified in Section 09-010 Fibre Optics.

2.3 VAULTS

.1 Vaults shall be as specified in Section 09-010 Fibre Optics.

PART 3: EXECUTION

3.1 TRAFFIC ACCOMMODATION

.1 The coordination of the Work and road closures are the sole responsibility of the Contractor, with approval required from the City prior to proceeding.

.2 Any closure or blockage of traffic shall be as brief as possible and at no time shall any one city block be isolated from emergency services except during the actual carrying out of the Work. During any such closure, the Contractor shall at his sole expense, provide and maintain a signed detour route for the safe movement of both vehicular and pedestrian traffic.

.3 The Contractor shall coordinate the Work such that all affected commercial properties will have access during regular business hours (note regular business hours may vary).

.4 The Contractor shall coordinate the Work to minimize disruption to residential driveway and parking access. The Contractor shall provide temporary access to all driveways not immediately adjacent to an open excavation during evenings, weekends, holidays and other times in which the Contractor is not working.

.5 All traffic control devices including signs, barricades, channelling, and other devices shall conform to the requirements of Section 01570, Traffic Control, and the City of Brandon Traffic Control Manual for Temporary Conditions, and the Manitoba Infrastructure and Transportation Work Zone Traffic Control Manual.

.1 Any installed device that, in the opinion of the City does not comply with the aforementioned standards shall be removed promptly and replaced. The Contractor shall ensure that there are sufficient devices on hand to adequately protect all Sites during the performance of the Work and shall designate a representative to regularly maintain such devices.

.6 The Contractor shall prepare a detailed traffic control plan which satisfied the requirements noted herein, and provide to the City of review and approval a minimum of five (5) days prior to the scheduled start date of the Work.

.7 Prior to any road closure, the Contractor shall give a minimum of forty-eight (48) hours written notice to the City in order to advise all emergency services, Brandon Transit, City of Brandon Public Works, and the local media indicating the location, duration, and nature of the road closure.

3.2 DE-WATERING

.1 De-watering of the Site is expected to be required. The method and means of de-watering all excavations shall be the Contractor's sole responsibility with approval required from the City for location of discharge.

3.3 EXCAVATION, BEDDING, & BACKFILL

.1 Excavation and Backfill shall be as specified in Section 02210, Excavation, Bedding & Backfill, the Scope of Work, and as indicated on the Unit Price Schedule or on the Drawings.

.2 Bedding material shall be Bedding Sand as specified in Section 02210, Excavation, Bedding & Backfill.

.3 Bedding Gravel as specified in Section 02210, Excavation, Bedding & Backfill, may be used as an alternative to Bedding Sand provided the base of the excavation is, in the opinion of the City, significantly saturated and softened such that any installation bedded on Bedding Sand may not receive adequate support.

.1 Bedding Gravel may not be used as an alternative to Water Control as specified in Section 02210, Excavation, Bedding & Backfill. If standing water exists in the excavation, the Contractor shall drain the excavation as specified in Section 02210, Excavation, Bedding & Backfill, prior to placement of bedding material.

.2 Bedding Gravel, if approved for use by the City, shall have a minimum depth of 0.150 metres and shall be installed to the spring line of the pipe. Bedding Sand shall be used from the spring line of the pipe to 0.300 metres above the top of pipe.

3.4 WALL PENETRATION REPAIR

.1 Wall penetration shall be repaired with a non-shrink cementitious grout and must have a minimum 28-day strength of 55 mPa.

.2 The exterior surface of the repaired foundation wall shall be waterproofed with a liquid-applied rubberized membrane system, such as Henry Rubberized Membrane or an approved equivalent. The membrane shall be installed in accordance with the manufacturer's current recommendations, including all surface preparation, application, and curing requirements.

3.5 CONDUIT

.1 Conduit shall be as specified in Section 09-010 Fibre Optics.

3.6 FIBRE OPTIC CABLE

.1 Fibre Optic Cable shall be as specified in Section 09-010 Fibre Optics.

3.7 REMOVAL OF EXISTING VAULT

.1 Removal of existing vaults shall consist of the following:

.1 Pull existing cable slack into the vault located west of the vault to be removed.

.2 Extend existing HDPE conduit as required for building termination

3.8 BUILDING TERMINATION

.1 Building termination shall be as specified in section 09-010 Fibre optics.

3.9 SIDEWALK REPAIR

.1 Sidewalk repairs shall be as specified in section 02514 Concrete Construction.

.2 Any paving stones removed outside of the proposed sidewalk repair area shall be replaced to their existing state.

END OF SECTION

SECTION 01003 MEASUREMENT & PAYMENT

PART 1: GENERAL

1.1 OTHER CONTRACT DOCUMENTS

.1 The General Conditions of the Contract, the Supplemental Conditions, Specifications, and Drawings attached hereto shall apply to and be part of this Section. If there is any conflict between this Section and either of the above, this Section shall govern.

1.2 MATERIALS SUPPLIED BY CITY

.1 Supply of materials is by Contractor unless noted in the Drawings or Unit Price Schedule as 'Supply by City'. Where Materials are supplied by City, only the specific item identified will be supplied. All other tools, parts or materials required (including restraint devices) to install materials shall be supplied by the Contractor.

1.3 MEASUREMENT

.1 Items measured in lineal metres shall be measured to the nearest whole metre.

.2 Items measured in vertical metres shall be measured to the nearest 0.1 metre.

.3 Items measured in square metres shall be measured to the nearest square metre.

.4 Items measured in cubic metres shall be measured to the nearest cubic metre.

PART 2: PRODUCTS

NONE

PART 3: EXECUTION

3.1 TRAFFIC ACCOMMODATION

.1 There will be no measurement made for Traffic Accommodations as described in Section 01002 Scope of Work.

.2 Payment for Traffic Accommodations will be included in the price for 'Excavation & Sidewalk Repair' which shall be payment in full for those operations described in the Scope of Work and as shown on the drawings.

3.2 DE-WATERING

.1 There will be no measurement made for De-watering as described in Section 01002 Scope of Work.

.2 Payment for De-watering will be included in the price for excavation & sidewalk repair' which shall be payment in full for those operations described in the Scope of Work and as shown on the drawings.

3.3 EXCAVATION, BEDDING, & BACKFILL

.1 There will be no measurement made for Excavation, Bedding & Backfill as described in Section 01002 Scope of Work.

.2 Payment for Excavation, Bedding, & Backfill will be included in the price for 'excavation & sidewalk repair' which shall be payment in full for those operations described in the Scope of Work and as shown on the drawings include but not limited to:

.1 Removal and disposal of unsuitable material, transportation, the supply and installation of bedding sand or bedding gravel.

.3 Additional bedding sand of bedding gravel required at manholes structures shall be incidental to the supply and installation of the structure.

3.4 WALL PENETRATION REPAIR

.1 There will be no measurement made for Wall Penetration Repair as described in Section 01002 Scope of Work.

.2 Payment for Foundation repair will be included in the price for 'Foundation Waterproofing' which shall be payment in full for those operations described in the Scope of Work and as shown on the drawings.

3.5 CONDUIT

.1 There will be no measurement made for conduit as described in Section 01002 Scope of Work.

.2 Payment for Conduit will be included in the price for 'Fibre optical routing & Vault removal' which shall be payment in full for those operations described in the Scope of Work and as shown on the drawings.

3.6 FIBRE OPTIC CABLE

.1 There will be no measurement made for Fibre optic Cable as described in Section 01002 Scope of Work.

.2 Payment for Fibre Optic Cable will be included in the price for ''Fibre optical routing & Vault removal'' which shall be payment in full for those operations described in the Scope of Work and as shown on the drawings.

3.7 REMOVAL OF EXISTING VAULT

.1 There will be no measurement made for removal of existing vault as described in Section 01002 Scope of Work.

.2 Payment for Temporary Pumping will be included in the price for 'Fibre optical routing & Vault removal' which shall be payment in full for those operations described in the Scope of Work and as shown on the drawings.

3.8 BUILDING TERMINATIONS

.3 There will be no measurement made for Building Terminations as described in Section 01002 Scope of Work.

.4 Payment for Building Terminations will be included in the price for 'Fibre optical routing & Vault removal' which shall be payment in full for those operations described in the Scope of Work and as shown on the drawings.

3.9 SIDEWALK REPAIR

.1 There will be no measurement made for Sidewalk Repair as described in Section 01002 Scope of Work.

.2 Payment for Repairs will be included in the price for ‘Excavation & Sidewalk repair’ which shall be payment in full for those operations described in the Scope of Work and as shown on the drawings.

END OF SECTION

CITY OF BRANDON
BID FORM

QUOTATION: Item: #L-42

SUBJECT: A.R. McDiarmid Civic Complex Fibre Relocation & Foundation Waterproofing

CLOSING DAY: 5:00:00 pm local Brandon time, Thursday, October 29, 2026

I, _____ representing _____
(Name) (Company Name)

of _____ _____ _____ _____
(Mailing Address) (City) (Province) (Postal Code)

_____ _____ _____
(Phone Number) (Fax Number) (G.S.T Registration Number)

Email Address: _____

I am authorized to bind the corporation and do hereby submit this as my price on the above-noted item.

The total amount of my bid price, in Canadian Funds, including all duties and applicable fees, F.O.B., A.R. McDiarmid Civic Complex, 638 Princess Avenue, Brandon, Manitoba, Canada is:

A.R. McDiarmid Civic Complex Fibre Relocation & Foundation Waterproofing

Item	Base Price	G.S.T. (5%)	MB R.S.T. (7%) where applicable	Total
Fibre Optics Routing & Vault Removal				
Foundation Waterproofing				
			Total Bid Price	$

Optional Work

Item	Base Price	G.S.T. (5%)	MB R.S.T. (7%) where applicable	Total
Excavation & Sidewalk Repair				
			Total Bid Price	$

Completion date in number of calendar days from receipt of purchase order: _____ days

_____
(Bidder to Initial)

…/2

Contact information for two (2) references whom you've provided the same or similar service to:

Company: _____ Company: _____

Contact Name: _____ Contact Name: _____

Contact #: _____ Contact #: _____

Workers Compensation #_____ must be current and in good standing.

Note: Review Section E Submittal Requirements to ensure all documentation is submitted.

We hereby acknowledge receipt of the following Addenda to the Quotation Documents:

Addendum No. _____ Date Received _____

Addendum No. _____ Date Received _____

Addendum No. _____ Date Received _____

_____ _____ _____

(Signature) (Date) (Witnessed by)*

I am authorized to bind the Corporation

_____

Print Name of Witness

*This document must be witnessed to be compliant.